BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

NAME OF THE WORK:- Improvements to Roads of Sahakaranagara A Block and E Block (Except Roads Executed by PWD & Road Infrastructure Department) in Ward No 07 Byatarayanapura.

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
1	1011.63	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.133, I.No.19.1 of PW, P&IWTD SR 2016-17)	cum	186.92	Rupees One Hundred Eighty Six and Ninety Two Paise Only
2	2127.05	Removing & Refixing Stone slabs of drains and Pointing in C.M(1:3) (P.No.25, I.No.5.33 of PW, P&IWTD SR 2016-17)	Sqm	80.56	Rupees Eighty and Fifty Six Paise Only
3	777.02	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 7.5cms thick (P.No.25, I.No.5.31.1 of PW, P&IWTD SR 2016-17)	Sqm	665.68	Rupees Six Hundred Sixty Five and Sixty Eight Paise Only
4	167.06	KSRRB M300-14. Excavation for roadwork in soil with hydraulic excavator of 0.90 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to embankment location and complete as per specifications. MORTH Specification No.301 (P.No.142, I.No.19.14 of PW,P&IWTD S.R 2016-17)	cum	148.76	Rupees One Hundred Forty Eight and Seventy Six Paise Only
5	167.06	KSRRB M 400-17, Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechaniqal mix plant carriage ' of mixed Material by tipper to site, laying in uniform layers with paver in sub- base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density.complete as per specifications. MORTH Specification No. 406 (P.No.157, I.No.20.18 of PW,P&IWTD SR 2016-17)	cum	1768.08	Rupees One Thousand Seven Hundred Sixty Eight and Eight Paise Only
6	1113.75	KSRRB M 500-6, Providing and applying primer coat with SS bitumen emulsion on prepared surface of granular Base such as WBM WMM including clearing of road surface and spraying primer at the rate of 0.60 kg\sqm using mechanical means complete as per specifications. As per MORTH specification clause No. 502 (P.No.160, I.No.21.6 of PW,P&IWTD SR 2016-17)	Sqm	27.56	Rupees Twenty Seven and Fifty Six Paise Only
7	10139.50	KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatement including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH Spec, Chapter 5 (P.No.160, I.No.21.2 of PW,P&IWTD SR 2016-17	Sqm	3.18	Rupees Three and Eighteen Paise Only
8	10139.50	KSRRB M500-7 : Providing and applying tack coat using 80/100 grade bitumen (VG10) on prepared black topped surfaces at 2.5 Kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.MORTH / Chapter 5 (P.No.160 I.No.21.7 of PW,P&IWTD SR of 2016-17)	Sqm	11.66	Rupees Eleven and Sixty Six Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the contractor

Executive Engine

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
9	405.58	KSRRB M500-19. Providing and laying bituminous concrete 40 mm compacted thickness with VG30 Bitumen grade using 40-60 HMP using crushed aggregates of grading II, premixed with bituminous binder at 6% of mix and filler, transporting the hot mix to work site, laying with a mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification clause No. 500.9 complete in all respects as per specifications. MORTH Specification No. 509 (P.No.164 of I.No.21.22.6 in PW,P&IWTD S.R 2016-17)	cum	7083.98	Rupees Seven Thousand Eighty Three and Ninety Eight Paise Only
10	381.12	KSRRB M800-13. Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 (P.No.197, I.No.24.15 of PW,P&IWTD SR 2016-17	Sqm	542.72	Rupees Five Hundred Forty Two and Seventy Two Paise Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'.

CONTRACTOR

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010